

**LANCASTER COUNTY ENGINEERING DEPARTMENT
CHANGE ORDER - SUPPLEMENTAL AGREEMENT No. 1**




DATE: 6/19/18	PROJECT NUMBER: 18-03
CONTRACTOR: Tim Sisco Construction LLC	LOCATION: Culvert Site B-76 on N 27th St North of Agnew Road
GROUPS OF WORK: Groups 1, 4, 5, and 10	STATION: NA
SUPPLEMENTAL TO CONTRACT FOR WORK ON PROJECT NAME: Culvert Maintenance 2018 (Phase I)	DATE OF ORIGINAL CONTRACT: 4/24/2018

WE HEREBY REQUEST APPROVAL OF CHANGES IN THE PLANS, SPECIFICATIONS, OR WORK NOT INCLUDED IN THE PLANS OR CONTRACT DESCRIBED AS FOLLOWS:

Added culvert replacement site.
Added portable restroom facilities to contract.

ESTIMATED CHANGES IN QUANTITIES OF ITEMS OF WORK AT CONTRACT OR AGREED UNIT PRICES

ITEM OF WORK	UNIT	INCREASED QUANTITY	DECREASED QUANTITY	CONTRACT UNIT PRICE	AGREED UNIT PRICE	INCREASED (+) OR DECREASED (-)
PART XVI (B-76)						
Group 1 - Grading						(+) 15,915.00
Group 4 - Culverts						(+) 10,489.50
Group 5 - Landscaping						(+) 6,132.00
Group 10 - General						(+) 780.00
Portable Restroom Facilities	Week	12.00	0.00	\$0.00	\$70.00	(+) 840.00
TOTAL NET INCREASE (+) or DECREASE (-)						(+) 34,156.50

APPROVED PROJECT ENGINEER 	For and in consideration of the prices set forth in this agreement, the Contractor agrees to complete the extra and additional work or reduced quantities of work described herein and accept the prices shown as full payment. The insurance, bond and items of the contract remain in full effect, except as specifically changed herein, and shall apply to this agreement.
APPROVED COUNTY ENGINEER 	NAME OF CONTRACTOR Tim Sisco
	AUTHORIZED BY (SIGNATURE) 

EXECUTED this _____ day of _____, 20_____.

APPROVED AS TO FORM THIS _____ DAY

OF _____ 20_____.

LANCASTER COUNTY ATTORNEY

LANCASTER COUNTY BOARD OF COMMISSIONERS

COUNTY COMMISSIONERS

CHANGE ORDER – SUPPLEMENTAL AGREEMENT No. 1

ESTIMATED CHANGES IN QUANTITIES OF ITEMS OF WORK AT CONTRACT OR AGREED UNIT PRICES

ITEM OF WORK	UNIT	INCREASED QUANTITY	DECREASED QUANTITY	CONTRACT UNIT PRICE	AGREED UNIT PRICE	INCREASED (+) OR DECREASED (-)
Part XVI (B-76) Group 1 - Grading						
General Clearing And Grubbing	Lump Sum	1	0.00	\$0.00	\$2,000.00	(+) 2,000.00
Excavation (Established Quantity)	Cu.Yds.	373	0.00	\$0.00	\$5.00	(+) 1,865.00
Rock RipRap, Type B	Ton	80	0.00	\$0.00	\$56.00	(+) 4,480.00
Water	M.Gal	1.5	0.00	\$0.00	\$130.00	(+) 195.00
Crushed Rock Surface Course	Ton	96	0.00	\$0.00	\$36.50	(+) 3,504.00
Incorporating Crushed Rock Surfacing	Station	3.75	0.00	\$0.00	\$100.00	(+) 375.00
Salvaging and Placing Topsoil	Sq.Yds.	1748	0.00	\$0.00	\$2.00	(+) 3,496.00
Total Group 1 =						(+) 15,915.00
Part XVI (B-76) Group 4 - Culverts						
Excavation For Pipe, Pipe-Arch Culverts And Headwalls	Cu.Yds.	164	0.00	\$0.00	\$5.00	(+) 820.00
Class 47B-3000 Concrete For Headwalls	Cu.Yds.	2.33	0.00	\$0.00	\$1,050.00	(+) 2,446.50
Reinforcing Steel For Headwalls	Lbs.	201	0.00	\$0.00	\$3.00	(+) 603.00
Install 48" Culvert Pipe, Type 3 (County Furnished)	Lin. Ft.	82	0.00	\$0.00	\$50.00	(+) 4,100.00
Rental Of Crawler-Mounted Hydraulic Excavator, Fully Operated	Hour	4	0.00	\$0.00	\$180.00	(+) 720.00
Rental Of Front End Loader, Fully Operated	Hour	4	0.00	\$0.00	\$200.00	(+) 800.00
Rental Of Skid Loader, Fully Operated	Hour	4	0.00	\$0.00	\$100.00	(+) 400.00
Rental of Dump Truck, Fully Operated	Hour	4	0.00	\$0.00	\$150.00	(+) 600.00
Total Group 4 =						(+) 10,489.50
Part XVI (B-76) Group 5 - Landscaping						
Erosion Control, Type 1-D	1748	1748	0.00	\$0.00	\$2.00	(+) 3,496.00
Fabric Silt Fence, High Porosity	24	24	0.00	\$0.00	\$4.00	(+) 96.00
Fabric Silt Fence, Low Porosity	460	460	0.00	\$0.00	\$5.00	(+) 2,300.00
Erosion Checks, Type "Wattle"	48	48	0.00	\$0.00	\$5.00	(+) 240.00
Total Group 5 =						(+) 6,132.00
Part XVI (B-76) Group 10 - General						
Barricade, Type III	BarrDay	80	0.00	\$0.00	\$2.00	(+) 160.00
Construction Signs	SignDay	60	0.00	\$0.00	\$2.00	(+) 120.00
Mobilization (Part I)	Lump Sum	1	0.00	\$0.00	\$500.00	(+) 500.00
Total Group 10 =						(+) 780.00
SUB TOTAL						(+) 33,316.50